

PURCHASE ORDER

Vendor Address

S K Interior

Ground Floor, Shop No. 68, Internity Mall, L.B.S Marg, Near Tin Hat

Naka Wagle Estate

Thane

400604 Maharashtra

India

GSTIN 27ABKPY1132A1ZW

Deliver To

CLINISUPPLIES INDIA PRIVATE LIMITED

Plot No.96, Medical Devices Park, DMIC Vikram Udyogpuri, Village

Narwar

Ujjain Madhya Pradesh 456664

India

GSTIN 27AARFN1565G1ZY

Purchase Order#

PO/26-27/0562

Date

09/07/2026

Delivery Date

Ref#

Clini Supplies-Plant
Office

Shipment preference

Project Name

Clini Supplies_Plant
Office_Ujjain

Project Category

Carpentry

Project Sub Category

Carpentry Work

#	Item	Description	Item/ Service Type	Make	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
1		Reception Table- Laminate finished: - Providing and constructing reception table of Overall size L 2150mm x W 750mm x H 750mm (worktop) / 1050mm (front fascia height) as per approved 3D view and drawings, with table top made of 25 mm thick commercial- grade plywood finished with 1mm thick laminate on other areas, underside finished with 0.8mm balancing laminate, and table edges in 38mm thick full round wood polished in melamine finish or as per approved design. Front side to be finished in 1mm	JOINERY /CARPA NTRY			1.00	80,000.00	7,200.00 9%	7,200.00 9%	0.00 0%	80,000.00

#	Item	Description	Item/ Service Type	Make	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
		laminate in approved shade and texture. Wire manager of 150mm x 75mm (or of approved size) to be constructed from 12mm thick commercial grade plywood with hardwood framework, finished externally in laminate and internally in melamine polish, including necessary cut-outs for cable routing. Supports to be made of 19mm marine-grade plywood with exposed surfaces in approved laminate and melamine polish. An attached pedestal unit to form an integral part of the table, consisting of two drawers with soft-close telescopic channels and one large bottom storage compartment with hinged shutter or pull-out drawer, fabricated from 19mm commercial grade plywood with visible surfaces finished in 1mm laminate and internal surfaces in 0.8mm laminate. All plywood to be of IS:303 commercial grade and all edges finished with 2mm ABS edge banding applied using hot-melt adhesive via edge-banding machine or heatex, including all hardware of approved make , necessary screws, fasteners, polishing, cutting, fixing, making good all damages, and completing the work as per approved design and specifications.									
2		Conference Room Table- Corian Finished:- Providing, fabricating, supplying and	JOINERY /CARPENTRY			1.00	13,500.00	1,215.00 9%	1,215.00 9%	0.00 0%	13,500.00

#	Item	fasteners, cutting, polishing, and finishing included to complete the work in all respects as per approved design and specifications.	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
3		Customised Ledge Sofa Seating:- Providing and fixing cushioned ledge seating of size (Running length) X 450 mm (Depth) X 450 mm (Height) as per detailed architectural drawings. The base structure shall be fabricated from 19 mm thick commercial-grade plywood conforming to IS:303, finished externally with 1.0 mm thick laminate of approved shade and texture as selected by the Architect. All exposed edges shall be sealed using 2 mm thick ABS edge banding tape, machine-applied with Heatex edge bander and hand router for a clean and durable finish. The seating shall be provided with a 100 mm thick cushion, made using high-density premium quality foam (minimum 40 density) and upholstered in fabric of approved make, colour, and texture as per selection. The entire unit shall be fixed in true line, level, and plumb and executed as per detailed drawings and instructions of the Architect/Engineer-in-Charge. Basic Price of Fabric: ₹400 per Sqm Basic Price of Laminate: ₹80 per Sqft"	JOINERY /CARPA NTRY			53.00	3,400.00	16,218.00 9%	16,218.00 9%	0.00 0%	1,80,200.00

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
4		12 mm thk Ply Cladding:- "Providing and fixing 12 mm thick commercial-grade plywood cladding of approved make, ISI- marked and conforming to IS:303, over the existing aluminium/wooden/M S framework/Wall, in proper line, level, and plumb, including measuring and cutting to required size and shape, securely fixed using approved quality countersunk wood screws/nails at regular intervals to ensure a firm and flush installation, with all exposed edges finished smooth and aligned, corner joints properly mitred or butt-jointed as per design intent, and surface made ready to receive final finishing (laminate/veneer/pain t/gypsum as applicable), including all tools, labour, fasteners, handling, cutouts, staging/scaffolding if required, and complete in all respects as per detailed drawings and site instructions.	JOINERY /CARPA NTRY			1,570. 00	130.00	18,369.0 0 9%	18,369.0 0 9%	0.00 0%	2,04,100.0 0

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
5		MDF Wall Panelling:- Providing and fixing 12 mm thick commercial-grade MDF panelling of approved make, ISI-marked and conforming to relevant standards IS:12406, over the existing aluminium/wooden/M S framework or wall surface, in true line, level, and plumb, including measurement, marking, and cutting to the required size and shape. Panels shall be securely fixed using approved quality countersunk screws or adhesive (as applicable) at regular intervals to ensure a firm and flush installation. All exposed edges shall be properly finished, smoothened, and aligned; corner joints shall be mitred or butt-jointed as per design requirements. The surface shall be prepared for final finishing (laminate/veneer/paint/gypsum as applicable). The rate shall include all necessary tools, labour, fasteners, cutouts, edge finishing, staging/scaffolding if required, and shall be complete in all respects as per approved drawings and site instructions.	JOINERY /CARPA NTRY			150.00	130.00	1,755.00 9%	1,755.00 9%	0.00 0%	19,500.00

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
6		MDF Boxing:- Providing and fixing decorative MDF boxing on right side wall in required curved / rounded / multilayers free-flow as per approved design and drawings, comprising framework made of kiln seasoned sal wood battens of minimum 50mm x 25mm section treated with anti-termite solution, fixed to wall with dash fasteners at 600mm c/c both ways; over the framework providing and fixing 12mm thick BWP grade plywood conforming to IS: 710 as base substrate, and further forming required curved / semi-circular / custom shaped boxing using 18mm thick HDHMR / Exterior Grade MDF board conforming to IS 12406, including cutting, CNC routing, groove making, kerf cutting for bending wherever required to achieve smooth curvature, edge rounding, lamination in layers where necessary to maintain structural rigidity, complete with necessary screws, adhesives and proper alignment; all exposed edges to be finished with 2mm thick PVC edge banding fixed with Heatex adhesive; surface to be prepared with putty, sanding, including making shadow gaps, sealing joints, scaffolding, cutting, wastage and making good adjoining surfaces, complete in	JOINERY /CARPA NTRY			104.00	300.00	2,808.00 9%	2,808.00 9%	0.00 0%	31,200.00

#	Item	Description	Item/ Service Type	Make	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
7		all respects as per approved drawings and site instructions. MDF Wall Panelling (CNC Cut):- Providing and fixing CNC-cut MDF wall panelling using 12 mm thick commercial-grade MDF boards of approved make, ISI-marked and conforming to IS:12406, fixed over 12 mm thick ply backing, ensuring proper line, level, and plumb. Panels shall be precision-cut using CNC routing as per approved design patterns and drawings, with clean, burr-free edges and consistent detailing . The MDF panels shall be securely fixed using countersunk screws or adhesive as per manufacturer's recommendation, ensuring a flush and firm installation. All cut edges and surfaces shall be finished smooth and prepared to receive final finishing (PU paint / Duco / laminate / veneer / polish as applicable). The scope includes design approval, CNC routing, handling, transportation, edge treatment, proper joint alignment (butt or mitred), cutouts for services if required, tools, labour, staging/scaffolding, and complete all in all respects as per approved architectural drawings and site instructions.	JOINERY /CARPENTRY			200.00	350.00	6,300.00 9%	6,300.00 9%	0.00 0%	70,000.00
8		MDF Beading with polish:- Providing and fixing decorative MDF beading with edge moulding and	JOINERY /CARPENTRY			110.00	70.00	693.00 9%	693.00 9%	0.00 0%	7,700.00

#	Item	shall be complete in all respects as per approved Description	Item/ Service Type	Make	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
9		architectural drawings and site instructions. Acoustical Wall panelling (CNC Cut):- Providing and fixing 9 mm thick acoustical PET panels of approved make and colour, CNC machine-cut with groove patterns and shapes as per detailed architectural drawings, fixed over 6 mm thick MDF backing conforming to IS:12406. The ply shall be securely fixed to the existing framework/wall using approved screws or fasteners in proper line, level, and alignment. PET panels shall be fixed over the ply using approved adhesive or concealed mechanical fasteners, ensuring seamless finish, precision joints, and flush mounting. The system shall include all necessary cut-outs for lights and MEP services, along with proper edge finishing and clean detailing. The PET panels shall have a minimum NRC of 0.7 suitable for interior acoustic applications. The rate shall include supply, fabrication, cutting, grooving, fixing, and all materials, labour, tools, and complete installation as per drawings and instructions of the Architect/Engineer-in-Charge.(Non-MDF Backing)	JOINERY /CARPANTRY			250.00	240.00	5,400.00 9%	5,400.00 9%	0.00 0%	60,000.00

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
1 0		Laminate Wall Panelling:- "Providing and fixing laminate panelling over existing GI framework, including cladding with 12 mm thick commercial- grade plywood of approved make, conforming to IS:303, securely fixed to the GI framework with countersunk screws in proper line, level and plumb, and finished with 1 mm thick laminate of approved shade and texture; pasted over the ply surface using approved adhesive, with all exposed edges finished using 2 mm thick ABS edge banding to be pasted by hand router machine and heatex, including necessary cut-outs for electrical light points, switches, sockets, and junction boxes as per architectural design and MEP coordination, ensuring clean and accurate openings, seamless alignment, and smooth finish, complete in all respects as per detailed drawings and instructions of the Architect/Engineer-in- Charge.	JOINERY /CARPA NTRY			421.00	275.00	10,419.7 5 9%	10,419.7 5 9%	0.00 0%	1,15,775.0 0

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
1 1		Fluted WPC panelling:- Providing and fixing decorative PVC/WPC fluted wall panelling of 12 mm thickness in approved shade and texture, fixed over 12 mm thick commercial grade plywood backing (IS:303) using adhesive and concealed stainless steel screws, including matching corner trims, edge profiles, and skirting where required, ensuring panels are cut, aligned, and joined with tongue-and-groove interlocking system for a seamless finish. All exposed edges shall be finished with matching trims, junctions at floor, ceiling, and corners made neat, and necessary cut-outs provided for electrical fittings as per drawings. The work shall include supply and fixing of plywood backing, surface preparation, adhesive application, installation of panels, and making good all damages complete in all respects as per manufacturer's specifications and engineer's approval. Basic Price of PVC fluted panels : 150 per sft	JOINERY /CARPA NTRY			104.00	350.00	3,276.00 9%	3,276.00 9%	0.00 0%	36,400.00

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
1 2		Pelmet:- "Providing and fixing pelmet of size 150 mm (H) x 150 mm (D) or as per site conditions, made from 19 mm thick Exterior Grade MDF board conforming to IS:12406 for both vertical and horizontal members, fixed along walls and partitions with proper alignment. The pelmet shall be supported at regular intervals (not exceeding 1000 mm c/c) using concealed MS brackets, wooden cleats, or approved framing system, ensuring stability, straightness, and a clean finish. All exposed surfaces shall be finished with paint of approved shade and texture (PU / enamel / emulsion as specified) — paint cost to be considered separately — with proper surface preparation including smooth sanding, edge sealing, and primer application prior to final finish. The rate shall include all materials, hardware, supports, labour, scaffolding, and installation complete in all respects as per approved drawings and as directed by the Architect.	JOINERY /CARPA NTRY			37.00	275.00	915.75 9%	915.75 9%	0.00 0%	10,175.00

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
1 3		Baffle Ceiling:- Providing and fixing suspended baffle ceiling comprising factory-fabricated GI baffles of size 25 mm wide x 75 mm deep, made from 0.6–0.8 mm thick galvanized steel sheet, powder coated in approved woodgrain or plain colour finish, installed at 25 mm clear gap between baffles, aligned in straight grid across the ceiling area. Baffles shall be securely fixed to a 25 mm x 25 mm x 1.2 mm thick MS square tube framework, pre-fabricated and suspended from RCC slab using 8 mm dia. MS rod hangers with dash fasteners at maximum 900 mm x 900 mm grid spacing. Each baffle shall be clipped/fixed to the MS frame using concealed suspension clips or U-clips to maintain accurate spacing and level. Integrated linear LED lights shall be installed in selected baffle gaps as per approved lighting layout, with necessary provisions for wiring and cut-outs. All suspension and framework components shall be zinc-chromate primer-coated and finished with black enamel paint for corrosion resistance. The rate shall include material, powder-coated finish, fabrication, supports, fixing hardware, lighting cut-outs, scaffolding, and installation complete as per approved	JOINERY /CARPA NTRY			195.00	450.00	7,897.50 9%	7,897.50 9%	0.00 0%	87,750.00

#	Item	design and architectural intent. Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
1		Low Height Storages:-	TYPE			40.00	1,250.00	4,500.00	4,500.00	0.00	50,000.00
4		Providing and constructing low height storage unit of 400 mm to 600 mm depth and 750 mm overall height as per detailed drawings, fabricated using 19 mm thick commercial-grade plywood of approved make conforming to IS:303 for the carcass, shelves, and shutters. All external visible surfaces shall be finished with 1.0 mm thick laminate, and all internal surfaces shall be finished with 0.8 mm thick balancing laminate of approved shade and texture, applied using synthetic resin adhesive. All exposed internal and external plywood edges shall be finished with 2 mm thick PVC edge banding of matching colour, machine-applied using Heatex and hand router for a seamless and durable finish. The unit shall include all necessary hardware such as soft-close hinges, locks, handles, tower bolts or ball catches, magnetic stoppers, and any other accessories required for smooth functioning, fitted as per detailed architectural drawings. The work shall be complete in all respects as per design, site conditions, and instructions of the Architect/Engineer-in-Charge. Laminate Basic Price : 80 per sft	/CARPA NTRY					9%	9%	0%	

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
1 5		Full Height Storages:- "Providing and fabricating full-height vertical storage unit as per architectural design and image reference, constructed using 19 mm thick commercial-grade plywood conforming to IS:303 for all vertical and horizontal members and 8 mm thick commercial plywood for back panels. All visible external surfaces of shutters shall be finished with 1.0 mm thick laminate in woodgrain texture or approved plain shade and internal surfaces with 0.8 mm thick laminate. Exposed edges to be machine-banded with 2 mm thick matching PVC edge banding using Heatex edge bander and neatly finished with hand router. Shutters to be fitted with soft-close concealed hinges and long vertical handles in black or approved finish. Unit shall be fabricated and installed true to line, level, and plumb, complete with necessary hardware and accessories, as per final design and instructions of the Architect/Engineer-in-Charge. Laminate Basic Price: ₹80/sq.ft	JOINERY /CARPA NTRY			100.00	1,250.00	11,250.00 9%	11,250.00 9%	0.00 0%	1,25,000.00
1 6		Open Display Storages:- Providing and constructing a custom open-grid display storage unit in true line, level, and alignment as per the 3D visual and	JOINERY /CARPA NTRY			111.00	1,250.00	12,487.50 9%	12,487.50 9%	0.00 0%	1,38,750.00

#	Item	architectural drawings, comprising a carcass and shelves fabricated from 19 mm thick commercial grade plywood conforming to IS 303, with a back panel made of minimum 12 mm thick plywood for enhanced structural rigidity. All visible external and internal niche surfaces shall be finished with 1.0 mm thick premium wood-grain laminate of approved make and shade, while non-visible surfaces shall be finished with balancing laminate to ensure stability. The unit shall be designed with integrated provisions for LED strip lighting, including factory-made precision grooves/recesses with frosted diffusers in each shelf and concealed internal conduits or pre-drilled routing within the carcass for seamless wiring. All exposed edges shall be finished with 2 mm thick PVC edge banding bonded with EVA hot-melt adhesive. The assembly shall use concealed joinery such as mini-fix or dowels to maintain the aesthetic of the open niches. The work includes all cutting, fabrication, assembly, hardware such as shelf supports and levelers, and making the unit ready for final electrical installation, completing the item in all respects as per the architect's instructions	Item/ Service Type	Make	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
17	Full Height Toy Store:- Providing and fixing custom-built Toy storage-integrated		JOINERY /CARPENTRY			181.00	1,250.00	20,362.50 9%	20,362.50 9%	0.00 0%	2,26,250.00

#	Item	Description	Item/ Service Type	Make	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
		cushioned ledge seating as per the 3D visual and detailed architectural drawings. The base cabinet structure shall be fabricated from 19 mm thick commercial-grade plywood conforming to IS: 303, featuring internal partitions and a back panel of minimum 12 mm thick plywood for structural integrity. The storage unit shall include shutters/drawers as per design, fitted with soft-close hinges or telescopic slides and recessed handles. The curved vertical profiles and arched fascias shall be constructed using flexible MDF/plywood to achieve a smooth, seamless radius. All external visible surfaces shall be finished with high-quality PU (Polyurethane) paint or Duco finish in approved multi-color shades, while internal surfaces shall be finished with 0.8 mm thick laminate or white wash. All edges shall be perfectly sanded and finished to eliminate sharp corners for child safety. The seating shall be topped with a 75 mm to 100 mm thick cushion made of high-density premium quality foam (minimum 40 density), upholstered in approved fabric/leatherette. The entire assembly shall be fixed in true line, level, and plumb, including all hardware, joinery, and finishing as per the Architect's instructions.									
18		DB Shutter:-	JOINERY /CARPA MITDV			105.00	750.00	7,087.50 9%	7,087.50 9%	0.00 0%	78,750.00

#	Item	complete with cutting, fixing, making good all surrounding surfaces, and complete in all respects as per approved drawings, manufacturer's specifications, and directions of the Architect / Engineer-in-Charge.	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
19		Janitor Storage:- Providing, fabricating and installing janitor storage unit shutters and carcass constructed from 19 mm thick Marine Grade Plywood conforming to IS:710, including vertical and horizontal members forming a robust framework with internal adjustable shelves made from 19 mm thick Marine Ply, edges finished with 2 mm PVC edge banding, ensuring long-term durability in wet areas. All exposed external surfaces shall be finished with 1.0 mm thick laminate of approved make, shade and texture, and all internal surfaces finished with 0.8 mm thick laminate of approved shade. The cupboard shall include provision for storage of cleaning tools and chemicals, with dedicated sections for mop, broom, and bucket storage, including stainless steel mop holder and hooks where required. Shutters shall be provided with 3-way adjustable soft-close concealed hinges of approved make, SS handle set, magnetic catch, and Godrej or equivalent make locking arrangement. One shutter shall be provided with	JOINERY /CARP NTRY			100.00	950.00	8,550.00 9%	8,550.00 9%	0.00 0%	95,000.00

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
20		aluminium perforated ventilation grill (approx. 450 mm x 225 mm or as per drawing), powder coated in approved color to ensure proper ventilation and odor control. All hardware including screws, fasteners and adhesives shall be of corrosion-resistant quality and suitable for wet-use application. Installation shall be carried out in true line, plumb and level, making good all damages, as per approved drawings and instructions of Architect/Engineer-in-Charge, ensuring a clean and stable finish complete in all respects. Water Cooler Boxing Unit (With Storage & Shutter):- Providing and fixing customised water cooler boxing unit with integrated storage cabinet and shutter, as per approved drawings and design intent, made from 19 mm thick BWP-grade plywood conforming to IS:710, finished externally with 1.0 mm thick laminate or 12 mm thick fluted MDF in approved shade and texture, and internally with 0.8 mm thick laminate. All exposed edges shall be sealed with 2 mm thick PVC edge banding, machine-applied using Heatex. The unit shall incorporate a dedicated boxing space for the water cooler with properly sized openings, service cutouts, and ventilation grills for	JOINERY /CARPA NTRY			86.00	1,250.00	9,675.00 9%	9,675.00 9%	0.00 0%	1,07,500.0 0

#	Item	Description	Item/ Service Type	Make	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
2		heat dissipation, along with a storage compartment provided with shutter(s), complete with soft-close hinges, handles, magnetic catch, and internal shelf as required. Provision shall be made for water inlet and drain lines as per plumbing requirements. The design shall integrate seamlessly with adjoining pantry modules and shall include all necessary internal framing, supports, and back panels to ensure rigidity and clean alignment. All cutouts shall be machine-cut with smooth edges, accurately finished and sealed to prevent moisture ingress. The entire assembly shall be installed in proper line, level, and alignment, complete in all respects with all accessories, screws, fasteners, and as per manufacturer's specifications and directions of the Architect/Engineer-in-Charge.									
1		Undercounter Storage with Shutters:- Providing and fixing undercounter storage comprising shutters and a set of drawers below wash basin and pantry counters, fabricated from 19 mm thick marine-grade plywood of approved make, conforming to IS:710, finished externally with 1.0 mm thick laminate or 12 mm thick fluted laminate and internally with 0.8 mm thick laminate of approved shade and texture, applied using synthetic resin adhesive. All exposed	JOINERY /CARPENTRY			100.00	1,150.00	10,350.00 9%	10,350.00 9%	0.00 0%	1,15,000.00

[illegible]

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
2 2		Over Head Storages:- Providing and fixing overhead pantry storage units upto 450 mm depth and height as per detailed drawings, fabricated using 19 mm thick commercial-grade plywood of approved make conforming to IS:303 for top, bottom, sides, shutters, and intermediate shelves, and 8 mm thick commercial plywood for the back panel. All external visible surfaces shall be finished with 1.0 mm thick laminate, and internal surfaces with 0.8 mm thick balancing laminate of approved shade and texture, applied using synthetic resin adhesive. All exposed edges shall be finished with 2 mm thick PVC edge banding of matching colour, machine-applied using Heatex and hand router. The unit shall be securely fixed to the wall or supporting surface using suitable anchor fasteners and concealed brackets, and shall include all necessary hardware such as soft-close hinges, SS handles (minimum 100 mm), magnetic ball catches, tower bolts, and locks (if required), complete with all labour, materials, tools, and accessories, finished in proper line, level, and plumb, as per drawings and instructions of the Architect/Engineer-in-Charge.	JOINERY /CARPA NTRY			100.00	950.00	8,550.00 9%	8,550.00 9%	0.00 0%	95,000.00

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
2 3		Modesty Panel:- Providing and fixing modesty panel below washroom counter made from HDFboard of 12 mm (as specified in drawings), exterior-grade, water-resistant, scratch-resistant and anti-fungal, of approved make and shade. The panel shall be machine-cut with smooth edges, chamfered where required, and securely fixed using SS brackets/cleats, countersunk screws and nylon sleeves, ensuring rigid installation without visible fixings on the front face. All cut edges shall be sealed with matching edge treatment to prevent moisture ingress. The modesty panel shall be installed in perfect line, level and alignment with the countertop and surrounding finishes, complete in all respects as per manufacturer's specifications and as directed by the Architect/Engineer-in-Charge.	JOINERY /CARPA NTRY			30.00	450.00	1,215.00 9%	1,215.00 9%	0.00 0%	13,500.00

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
2 4		Back Painted Glass Cladding:- Providing and installing back-painted (lacquered) float glass of approved shade and finish 5mm thick , non-toughened type, fixed over a base of existing 12 mm thick commercial-grade plywood mounted on existing framework or wall as per site conditions. The glass shall be of uniform thickness, free from waves or defects, and cut to size with polished edges as required. Installation shall be carried out using high-bond strength 3M double-sided adhesive tape and neutral cure silicone adhesive of approved make, ensuring proper alignment and firm bonding to the ply substrate. The rate shall include cost of all materials, labour, edge polishing, necessary scaffolding (if any), transportation, handling, and wastage of glass, complete in all respects as per drawing and directions of the Architect/Engineer-in-Charge.	JOINERY /CARPA NTRY			528.00	370.00	17,582.4 0 9%	17,582.4 0 9%	0.00 0%	1,95,360.0 0

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
2 5		Mirror Cladding:- Providing and installing 6 mm thick mirror of approved make and quality, fixed over existing 6 mm thick commercial-grade plywood backing, which shall in turn be mounted on a framework made of 15 mm x 15 mm section as per site conditions and approved design. The mirror shall be factory-cut to required size and shape with machine-polished edges and securely fixed to the plywood using neutral cure silicone adhesive of adequate bond strength, ensuring proper alignment and finish. The rate shall include all materials, labour, framework, edge polishing, handling, and installation. It shall also include any required D-mirroring, frosting, etching, or bevelling work on the mirror surface as per the final approved design and drawings, complete in all respects as directed by the Architect/Engineer-in-Charge.	JOINERY /CARPA NTRY			494.00	250.00	11,115.0 0 9%	11,115.0 0 9%	0.00 0%	1,23,500.0 0

#	Item	Description	Item/ Service Type	Mak e	HSN/ SAC	Qty	Rate	CGST	SGST	IGST	Amount
2 6		12 mm thk MDF Patta With Grooves:- Providing and fixing 12 mm thick MDF patta support of 100 to 150 mm width, made from commercial-grade MDF, fixed along the running length including making 6 mm wide x upto 6 mm deep groove with the sideby gypsum partitions as per site requirements to support glass partitions and other installations. The patta shall be securely anchored to the floor/wall using approved screws, fasteners, or anchor bolts at regular intervals to ensure firm grip and load- bearing capacity.The work includes cutting, shaping, fixing, alignment, and finishing, polishing wherever required complete in all respects as per approved drawings and instructions of the Architect/Engineer-in- Charge.	JOINERY /CARPA NTRY			400.00	50.00	1,800.00 9%	1,800.00 9%	0.00 0%	20,000.00

Items in Total 5,571.00	Sub Total	22,99,910.00
	Discount(0.00%)	(-) 0.00
	SGST9 (9%):	2,06,991.90
	CGST9 (9%):	2,06,991.90
	Adjustment	0.20
	Total	₹27,13,894.00

Terms & Conditions

- General Terms:-
1. The amount is inclusive of all applicable taxes.
 2. All disputes arising from this agreement shall be subject to the exclusive jurisdiction of the courts in Ahmedabad.
 3. Input GST credit cannot be availed based on the Proforma invoice.
 4. The amount is in accordance with Square Feet (SQFT) / Running Feet (RFT) / NOS.
 5. All works shall be executed strictly as per approved drawings, BOQ, samples, finishes, mock-ups (if

- any), and site instructions issued by Needle & Thread Designs LLP.
6. Strict adherence to approved materials, finishes, hardware specifications, detailing, and workmanship standards is mandatory.
 7. Any compromise, deviation, or non-compliance in material quality, workmanship, finishing, or installation shall result in deduction from bills or rejection of work.
 8. Needle & Thread Designs LLP reserves the right to reject substandard carpentry work or accept the same at reduced rates. The decision of Needle & Thread Designs LLP shall be final and binding.

Scope of Work:-

1. The scope of work includes supply (if applicable), fabrication, installation, finishing, polishing, hardware fixing, rectification, documentation, and handover of all carpentry items as per approved drawings, BOQ, samples, and site instructions.
2. Execution of all fixed and loose furniture including cabinets, wardrobes, wall paneling, shutters, counters, storage units, partitions, and other carpentry works as specified.
3. Supply and fixing of plywood, MDF, HDHMR, laminates, veneers, finishes, and all allied materials as per approved make and specifications.
4. Supply and installation of all hardware fittings including hinges, channels, handles, locks, closers, and accessories.
5. Proper alignment, leveling, edge banding, joint finishing, polishing, lamination, veneer matching, and final finishing of all carpentry works.
6. Protection of finished carpentry works till final handover.

Material & Execution Standards:-

1. All materials shall be brand new, unused, defect-free, and of approved make, grade, thickness, finish, and colour.
2. Approved product brands shall include, but not be limited to:
 - Plywood (BWP/BWR): Greenply / Century / Action Tesa
 - MDF / HDHMR: Action Tesa / Greenpanel / Merino
 - Laminates: Merino / Greenlam / Royale Touche
 - Veneers: Approved natural or engineered veneer as per approved sample
 - Hardware & Fittings: Hettich / Hafele / Blum / Dorset
 - Adhesives: Fevicol SH / Fevicol Marine
 - Polish / Paint / Finish: ICA / Asian Paints / Approved equivalent
3. All materials shall conform to relevant Indian Standards (IS) and manufacturer specifications.
4. In case any material under the contractor's scope is supplied or procured by Needle & Thread Designs LLP, the cost of such material shall be deducted from the total payable amount.
5. No duplicate, counterfeit, substandard, or non-approved material shall be used at site.

Testing & Handover:-

1. All carpentry works shall be inspected jointly and handed over in fully finished, aligned, functional, and defect-free condition.
2. Any issues related to alignment, finishing, polishing, lamination, veneer matching, joint gaps, warping, swelling, or hardware performance shall be rectified prior to handover.
3. All warranty cards, manuals, care instructions, and manufacturer certificates for hardware, fittings, and finishes shall be handed over at the time of final handover.

Safety Terms:-

1. The contractor shall comply with all applicable labour laws, safety regulations, EHS norms, and statutory requirements.
2. Child labour is strictly prohibited. Any violation shall lead to penalties, termination of contract, and legal action.
3. The contractor shall be fully responsible for the safety of all workers deployed at site.
4. Use of PPE including safety shoes, helmets, gloves, masks, and protective gear is mandatory.
5. Any damage caused to flooring, ceilings, walls, glass, furniture, fixtures, or adjacent works during execution shall be rectified at the contractor's cost.
6. Proper illumination, dust control, housekeeping, protection of adjacent works, and EHS compliance shall be maintained at all times.
7. Scaffolding shall be of sound and approved material, properly guarded, and capable of supporting at least four times the intended load.
8. Unsafe scaffolding is strictly prohibited.
9. Only approved metal, aluminium, or fiberglass ladders shall be used.
10. Damaged or unsafe ladders shall not be permitted at site.
11. Any hot work such as welding, cutting, or grinding shall be carried out only after obtaining a valid work permit and ensuring fire safety arrangements.
12. All carpentry machinery, saws, polishers, and rotating tools shall be fitted with proper guards and

safety mechanisms.

13. Unsafe machines shall be removed from site immediately.

Billing & Documentation:-

1. Any defective workmanship, improper alignment, finishing defects, polish issues, hardware malfunction, or damage identified before or after completion shall be rectified by the contractor at their own cost.
2. The contractor shall provide a minimum one (1) year warranty from the date of final handover for workmanship and installed hardware performance.
3. Test Data Sheets (TDS) and Material Test Certificates (MTC) shall be submitted as and when required.
4. Final billing, if applicable, shall be based on actual site measurements jointly verified and approved by Needle & Thread Designs LLP.
5. All invoices must be submitted in original form and emailed simultaneously, duly signed and stamped.
6. Advance payments shall be released only against submission of a valid GST-compliant Advance Receipt.
7. Payments shall be processed only after receipt of correct, complete, and compliant invoices.

Payment Terms:-

1. 25% Advance.
2. 50% Against RA Bill (payable upon achieving 80% work completion and certification by the Project Manager).
3. 20% After Installation and Snag Clearance.
4. 5% Retention payable after 6 months, subject to no defects or issues observed.

This Purchase Order for Clini Supplies-Plant Office.

S K Interior



{{Signature*}}

Authorized Signature